Bid Tabulation Report from Carson City Purchasing & Contracts
775-283-7137
http://www.carson.org/index.aspx?page=998

Notice to Contractors Bid# 1314-175 E-W Transmission Main Project - Ph. 2A-1

Date and Time of Opening: July 9, 2014 at 11:10 am

Description				Bidder # 1		Bidder # 2		Bidder #3	
				Peek Brothers Construction, Inc.		Sierra Nevada Construction, Inc.		A&K Earthmovers	
BONDING Provided, $, %, or no				5%		5%		5%	
BIDDER acknowledges receipt addendums				2		3		3	
	Description	Sched Value	Unit	Unit price	Total price	Unit price	Total price	Unit price	Total price
	Base Bid Items - Schedule A								
1	MOBILIZATION, DEMOBILIZATION AND CLEAN UP	1	LS	85,000.00	85,000.00	29,362.00	29,362.00	134,921.50	134,921.50
2	24" PVC C905, DR-25, 165 PSI Water Main - Fusible	1,430	LF	283.30	405,119.00	255.00	364,650.00	254.00	363,220.00
3	24" PVC C905, DR-25, 165 PSI Water Main - Bell & Spigot	2,340	LF	243.60	570,024.00	280.00	655,200.00	298.00	697,320.00
4	24" Butterfly Valve	4	EA	9,600.00	38,400.00	10,500.00	42,000.00	9,500.00	38,000.00
5	6" C900 Water Line	80	LF	57.00	4,560.00	5.00	400.00	66.00	5,280.00
6	Install Fire Hydrant Assembly	1	EA	10,500.00	10,500.00	12,500.00	12,500.00	11,500.00	11,500.00
7	Install Flush Valve Assembly	1	EA	11,500.00	11,500.00	12,500.00	12,500.00	11,500.00	11,500.00
8	Install 2" Air Release Valve Assembly & Appurtenances	5	EA	5,800.00	29,000.00	6,000.00	30,000.00	5,200.00	26,000.00
9	Install 4" SCH 40 PVC Fiber Optic Conduit w/ Pull String	11,400	LF	3.40	38,760.00	2.75	31,350.00	2.88	32,832.00
10	Install No. 9 Pull Box, Traffic Rated w/ Bolt Down Steel Cover	5	EA	3,200.00	16,000.00	1,800.00	9,000.00	2,000.00	10,000.00
11	Install 40" x36" Round "New Basis" Fiberglass/Polymer Concrete Fiber Optic Pull Box	2	EA	2,000.00	4,000.00	3,000.00	6,000.00	1,700.00	3,400.00
12	Construct Reinforced Concrete Headwall (10cy)	1	EA	12,500.00	12,500.00	13,000.00	13,000.00	18,500.00	18,500.00
13	Install Type 4R Curb Inlet	2	EA	1,750.00	3,500.00	2,500.00	5,000.00	1,700.00	3,400.00
14	Install 15" RCP Class IV Storm Drain	24	LF	100.00	2,400.00	110.00	2,640.00	70.00	1,680.00
15	Remove & Reconstruct 8" Wide Concrete Retaining Curb for Tree Ring and Volleyball Court Area.	190	LF	51.00	9,690.00	35.00	6,650.00	39.00	7,410.00
16	Remove & Reconstruct Type 1 Curb & Gutter	830	LF	30.00	24,900.00	30.00	24,900.00	30.00	24,900.00
17	Remove & Reconstruct PCC Sidewalk	7,020	SF	8.00	56,160.00	11.00	77,220.00	7.25	50,895.00
18	Construct Curb Ramps	1,290	SF	23.00	29,670.00	20.00	25,800.00	17.00	21,930.00
19	Remove & Reconstruct PCC Driveway	612	SF	9.20	5,630.40	16.00	9,792.00	12.50	7,650.00
20	Construct PCC Valley Gutter (4' Wide)	1,585	SF	8.90	14,106.50	11.00	17,435.00	10.50	16,642.50
21	4" Plantmix Bituminous Pavement Type 2 Aggregate, PG 64-28 NV w/ 9" Type 2 Agg Base	114,780	SF	3.20	367,296.00	4.60	527,988.00	4.45	510,771.00
22	Install AC Pavement Speed Bump	346	LF	16.60	5,743.60	6.00	2,076.00	6.00	2,076.00
23	Washington St. Permanent Pavement Patch (3"ac/6"ab)	1,140	SF	11.00	12,540.00	4.10	4,674.00	10.00	11,400.00
24	Saliman Rd. Permanent Pavement Patch (6"ac/9"ab)	2,520	SF	6.65	16,758.00	8.40	21,168.00	11.00	27,720.00
25	Saliman Rd. 1 1/2" Mill & Overlay	7,100	SF	3.02	21,442.00	2.60	18,460.00	2.40	17,040.00
26	Adjust Water Valve Box to Grade	3	EA	300.00	900.00	500.00	1,500.00	450.00	1,350.00
27	Waterborne Paint	1	LS	12,000.00	12,000.00	8,000.00	8,000.00	12,300.00	12,300.00
28	Install Sign & Post	12	EA	385.00	4,620.00	345.00	4,140.00	385.00	4,620.00
29	Install Concrete Parking Curbs	12	EA	100.00	1,200.00	50.00	600.00	130.00	1,560.00
30	DG Roadway Restoration with Stabilizer	4,980	SF	0.70	3,486.00	3.00	14,940.00	1.60	7,968.00
31	Sod Replacement (Includes soil preparation)	37,760	SF	1.20	45,312.00	1.20	45,312.00	1.40	52,864.00
32	2 Inch Caliper Trees	10	EA	550.00	5,500.00	275.00	2,750.00	655.00	6,550.00
33	Relocate Picnic Tables	2	EA	500.00	1,000.00	1,000.00	2,000.00	1,900.00	3,800.00
61	**Subtotal: Schedule A**				$1,869,217.500		2,029,007		2,147,000
62	Total Base Bid Price (Schedule A)				**1,869,217.50**		**2,029,007.00**		**2,147,000.00**
	Total Bid Price written in words? y/n				Y		Y		Y
	Bidder Information provided? y/n				Y		Y		Y
	Sub Contractors listed? y/n or none				5 (5%)		1 (5%), 2 (1%)		1(5%),7(1%), 7(O)
	Bid Document executed? y/n				Y		Y		Y
	END OF DOCUMENT								

Non-Responsive/Non-Responsible Bidder

Bid Tabulation Report from Carson City Purchasing & Contracts
775-283-7137
http://www.carson.org/index.aspx?page=998

Notice to Contractors Bid# 1314-175 E-W Transmission Main Project - Ph. 2A-1

Date and Time of Opening: July 9, 2014 at 11:10 am

Description		Sched Value	Unit	Bidder # 4 Unit price	Bidder # 4 Total price	Bidder # 5 Unit price	Bidder # 5 Total price	Bidder #6 Unit price	Bidder #6 Total price
				Spanish Springs Construction, Inc.					
BONDING Provided, $, %, or no				5%					
BIDDER acknowledges receipt addendums				2					
	Base Bid Items - Schedule A								
1	MOBILIZATION, DEMOBILIZATION AND CLEAN UP	1	LS	48,917.00	48,917.00		-		-
2	24" PVC C905, DR-25, 165 PSI Water Main - Fusible	1,430	LF	295.00	421,850.00		-		-
3	24" PVC C905, DR-25, 165 PSI Water Main - Bell & Spigot	2,340	LF	321.00	751,140.00		-		-
4	24" Butterfly Valve	4	EA	10,165.00	40,660.00		-		-
5	6" C900 Water Line	80	LF	43.00	3,440.00		-		-
6	Install Fire Hydrant Assembly	1	EA	12,300.00	12,300.00		-		-
7	Install Flush Valve Assembly	1	EA	15,800.00	15,800.00		-		-
8	Install 2" Air Release Valve Assembly & Appurtenances	5	EA	6,000.00	30,000.00		-		-
9	Install 4" SCH 40 PVC Fiber Optic Conduit w/ Pull String	11,400	LF	3.50	39,900.00		-		-
10	Install No. 9 Pull Box, Traffic Rated w/ Bolt Down Steel Cover	5	EA	2,140.00	10,700.00		-		-
11	Install 40" x36" Round "New Basis" Fiberglass/Polymer Concrete Fiber Optic Pull Box	2	EA	1,765.00	3,530.00		-		-
12	Construct Reinforced Concrete Headwall (10cy)	1	EA	14,980.00	14,980.00		-		-
13	Install Type 4R Curb Inlet	2	EA	2,247.00	4,494.00		-		-
14	Install 15" RCP Class IV Storm Drain	24	LF	69.50	1,668.00		-		-
15	Remove & Reconstruct 8" Wide Concrete Retaining Curb for Tree Ring and Volleyball Court Area.	190	LF	29.00	5,510.00		-		-
16	Remove & Reconstruct Type 1 Curb & Gutter	830	LF	30.00	24,900.00		-		-
17	Remove & Reconstruct PCC Sidewalk	7,020	SF	8.50	59,670.00		-		-
18	Construct Curb Ramps	1,290	SF	16.00	20,640.00		-		-
19	Remove & Reconstruct PCC Driveway	612	SF	14.00	8,568.00		-		-
20	Construct PCC Valley Gutter (4' Wide)	1,585	SF	14.00	22,190.00		-		-
21	4" Plantmix Bituminous Pavement Type 2 Aggregate, PG 64-28 NV w/ 9" Type 2 Agg Base	114,780	SF	5.00	573,900.00		-		-
22	Install AC Pavement Speed Bump	346	LF	16.00	5,536.00		-		-
23	Washington St. Permanent Pavement Patch (3"ac/6"ab)	1,140	SF	16.00	18,240.00		-		-
24	Saliman Rd. Permanent Pavement Patch (6"ac/9"ab)	2,520	SF	16.00	40,320.00		-		-
25	Saliman Rd. 1 1/2" Mill & Overlay	7,100	SF	2.50	17,750.00		-		-
26	Adjust Water Valve Box to Grade	3	EA	342.00	1,026.00		-		-
27	Waterborne Paint	1	LS	9,095.00	9,095.00		-		-
28	Install Sign & Post	12	EA	400.00	4,800.00		-		-
29	Install Concrete Parking Curbs	12	EA	59.00	708.00		-		-
30	DG Roadway Restoration with Stabilizer	4,980	SF	2.00	9,960.00		-		-
31	Sod Replacement (Includes soil preparation)	37,760	SF	2.50	94,400.00		-		-
32	2 Inch Caliper Trees	10	EA	400.00	4,000.00		-		-
33	Relocate Picnic Tables	2	EA	1,926.00	3,852.00		-		-
61	**Subtotal: Schedule A**				$2,324,444.000		-		-
62	Total Base Bid Price (Schedule A)				**2,324,444.00**		**-**		**-**
Total Bid Price written in words? y/n					Y				
Bidder Information provided? y/n					Y				
Sub Contractors listed? y/n or none					1 (5%)				
Bid Document executed? y/n					Y				

END OF DOCUMENT