

Attn Lee Plemel

Late Material 4.B



Shop Location:  
1617 Fairview Dr 26  
Carson City, NV 89701

Mailing Address:  
1617 Fairview Dr #26  
Carson City, NV 89701  
Nevada License # 35106A - MBL \$150,000

## Bill To

David Ruf  
2450 S. Curry St  
Carson City, NV 89703

## Proposal Agreement

Date

Estimate #

8/12/2016

5121

Web Site

www.mastercraft-painting.com

E-mail

office@mastercraft-painting.com

Phone #

775-883-3445

P.O. No.

Rep

KD

Concrete Sq ...

Item	Description
1a Ext Painting Commercial Estimate / Commercial 0 Commercial N P T 1 Ext Prep Comm	Estimate no charge Job set up and planning, OSHA, EPA and other job task that do not involve painting. Powerwash to provide a surface cleaned free of dust, dirt, oil, grease, wax chalky or loose paint, rust, mill scale, efflorescence, tannin acids or any other contamination that would affect the coatings. We will do our best to keep paint chips picked up during the prep process, but they are yours. Sand, scrape, re nail or screw to tighten up as needed, spot prime using top quality bonding primer as needed. Loose or bad caulking will be replaced with new 45 year acrylic caulking or proper sealants for the job. Control joints repaired as needed. Backer rod replaced as needed. Prep includes removing of lights, hardware etc and replacing when painting is complete. Mask and provide protection for all items not being painted. Landscaping, walks, roofs and windows etc, will be covered. Includes all time spent spreading drops, plastic, taping to protect surfaces during painting. Includes time for clean up of masking materials.
2 Ext Masking/Comm	Exterior finish applied by spray, backroll or backbrush 1st coat on siding, stucco or concrete tilt-up walls, spray 2nd coat as needed
3 Ext Finishes Comm	Trim applied by spray, brush, roll as needed ( 2 ) coats. Exterior doors, Man doors, Roll up doors painted. Accent colors applied to: None.
Materials Ext Commercial	PAINT MATERIALS: Generally we use Kelly Moore paint products: 1200 Flat finish or 1205 satin (low-luster) Finish on main body of Project. 1245 Satin (low-luster) or 1250 Semi-gloss on trim. All products subject to change to equivalent type from other manufacturers.
Sundries Commercial	MISCELLANEOUS PRODUCTS: Cleaning supplies, Kel-bond Primer, Caulking, tape, paper, plastic etc.
Special Job Cost Commercial ATBP Ext Commercial	Lifts, scaffolding, rigging, dumpster, power sanders, sani-huts etc.
Notes	AREAS TO BE PAINTED: Siding, Eaves, Fascia, Window Trim, Door Trim, Man Door(s) and Foundations (if currently painted). Notes & exclusions: This estimate is based on all new pre primed siding and trim and that all prep work will be completed prior to starting painting. Any extra prep work will be billed accordingly at our shop rate of \$50.00 per man per hour plus materials.

Terms

10% To book Remainder upon comp

Total 4,420<sup>00</sup>

Respectfully Submitted By